



# Absolute bearing/case vibration monitoring / Überwachung der absoluten Lager-/Gehäuseschwingung

## VIBROCONTROL 800

**Measuring ranges /**

**Messbereiche**

|                                  |                                     |
|----------------------------------|-------------------------------------|
| Vibration velocity / Geschw.     | 0-10 mm/s<br>0-20 mm/s<br>0-50 mm/s |
| Vibration amplitude / Schwingweg | 0-100 µm<br>0-200 µm<br>0-500 µm    |

- VC-868/0 - horizontal - Supply : 230/115 V AC
- VC-869/0 - vertical - Supply : 230/115 V AC
- VC-868/1 - horizontal - Supply : +24 V DC
- VC-869/1 - vertical - Supply : +24 V DC

### Accessories / Zubehör

- Option 1: PU-covered steel conduit – 3.7 m; dia. 17 mm
- Option 2: Terminal housing (6 terminals + 1 ground)

